

Complete House Framing Materials Checklist

Master checklist for a typical wood-framed residential house, from sill plates through roof framing. Final quantities, sizes, grades and connectors must be verified against the architectural, structural and truss plans.

Foundation-to-Framing Connection

- Pressure-treated sill plates
- Sill sealer / gasket
- Anchor bolts, nuts and washers or approved foundation anchors
- Hold-downs
- Straps
- Concrete / masonry anchors
- Construction adhesive where required
- Termite / capillary-break materials where specified

Floor System

- Dimensional floor joists or I-joists
- LVL beams
- Glulam beams
- PSL / LSL beams where engineered
- Bearing posts / columns
- Rim board / rim joists
- Squash blocks
- Web stiffeners
- Joist blocking
- Bridging where required
- Joist hangers
- Beam hangers
- Post caps
- Post bases
- Structural screws
- Hanger nails
- 23/32 in. or 3/4 in. tongue-and-groove subfloor
- Subfloor adhesive
- Subfloor nails / screws

Exterior Walls

- Bottom plates
- Standard studs
- Full-height studs
- King studs
- Jack / trimmer studs
- Cripple studs
- Corner studs / backing
- Double top plates
- Window sill material
- Window and door headers
- LVL headers where engineered
- Header spacers
- Wall blocking
- Fire blocking
- Ladder backing / interior wall backing
- Exterior wall sheathing - OSB, plywood or specified structural panels
- Sheathing nails
- Structural straps / ties
- Hold-down hardware
- Portal-frame hardware where required

Interior Walls

- Bottom plates
- Studs
- Double top plates
- Door headers
- Cripples
- Wall intersections / backing
- Cabinet backing
- Handrail backing
- TV backing if specified
- Shower / tub backing
- Vanity backing
- Closet / shelving backing
- Fire blocking
- Draft stopping where required
- Miscellaneous blocking

Tall Walls / Great Rooms

- Engineered or dimensional tall-wall studs
- LVL / LSL studs where engineered
- Large headers
- Beams
- Posts
- Hold-downs
- Straps
- Blocking
- Structural sheathing
- Engineered connections / fasteners

Stick-Framed Roof

- Rafters
- Ridge boards
- Structural ridge beams where required
- Ceiling joists
- Rafter ties
- Collar ties where required
- Valley rafters
- Hip rafters
- Jack rafters
- Lookouts
- Fly rafters
- Subfascia
- Overbuild / framing lumber
- Roof blocking
- Bird-block / eave blocking
- Posts supporting structural ridge beams

Truss Roof

- Common trusses
- Girder trusses
- Gable-end trusses
- Hip / jack trusses
- Valley trusses
- Attic trusses if applicable
- Truss bracing lumber
- Strongbacks
- Gable-end blocking
- Truss clips / ties
- Girder hangers
- Structural screws / bolts specified by truss engineering

Roof Sheathing

- 7/16 in., 1/2 in., 5/8 in. or specified OSB / plywood
- H-clips if required
- Roof sheathing nails
- Eave blocking
- Fascia / subfascia framing
- Lookout framing
- Ladder framing for gable overhangs

Beams and Posts

- LVL
- Glulam
- PSL
- LSL
- Built-up dimensional beams
- Steel beams
- Wood posts
- Engineered wood posts
- Steel columns
- Post bases
- Post caps
- Beam hangers
- Bearing plates
- Bolts
- Washers
- Structural screws
- Through-bolts

Stairs

- Stringer lumber
- Engineered stringers if specified
- Temporary construction treads
- Landings
- Landing joists
- Landing beams
- Landing posts
- Rim material
- Stair opening headers
- Hangers
- Blocking
- Guardrail backing
- Handrail backing

Decks, Porches and Exterior Framed Areas

- Pressure-treated ledger
- Ledger fasteners
- Joists
- Beams
- Posts
- Rim joists
- Blocking
- Joist hangers
- Hurricane ties
- Post bases
- Post caps
- Structural screws
- Flashing
- Deck sheathing if part of a waterproof / covered assembly

Hardware / Connectors

- Joist hangers
- I-joist hangers
- LVL / beam hangers
- Girder hangers
- Hurricane ties
- Truss clips
- Framing angles
- Straps
- Hold-downs
- Post bases
- Post caps
- Bearing plates
- Anchor bolts
- Expansion / wedge anchors
- Concrete screws
- Structural wood screws
- Ledger screws
- Through-bolts
- Nuts
- Washers
- Hanger nails
- Connector screws
- Specialty engineered connectors

Framing Fasteners

- 16d framing nails
- 10d nails
- 8d nails
- Sheathing nails
- Galvanized exterior nails
- Hanger nails
- Positive-placement connector nails
- Structural screws
- Wood screws
- Concrete fasteners
- Powder-actuated fasteners where permitted
- Bolts, nuts and washers
- Subfloor screws if used

Adhesives / Sealants

- Subfloor adhesive
- Construction adhesive
- Sill seal
- Approved sealant around penetrations where required
- Fire-blocking foam / caulk where appropriate

Temporary Framing Materials

- Bracing lumber
- Stakes
- Temporary guardrails
- Temporary stair treads
- Temporary handrails
- Truss bracing
- Wall bracing
- Scrap / blocking allowance

Recommended Lumber Takeoff Format

For bidding and material ordering, break dimensional lumber into exact lengths and quantities rather than using a single total.

Material	Length / Type	Quantity
2x4	92-5/8 in. studs	_____ pcs
2x4	104-5/8 in. studs	_____ pcs
2x4	116-5/8 in. studs	_____ pcs
2x4	8 ft / 10 ft / 12 ft / 14 ft / 16 ft	_____ pcs
2x6	Stud lengths and dimensional lengths	_____ pcs
2x8	As required	_____ pcs
2x10	As required	_____ pcs
2x12	As required	_____ pcs
PT lumber	By size and length	_____ pcs
I-joists	By depth and length	_____ pcs
Rim board	By depth and LF	_____ LF
LVL / Glulam	By width, depth and length	_____ pcs
Subfloor	By thickness	_____ sheets
Wall sheathing	By thickness	_____ sheets
Roof sheathing	By thickness	_____ sheets
Trusses	Per truss layout	_____ pcs
Hardware	Per structural / truss plans	_____

Important: This is a master checklist, not an engineered material schedule. Actual framing requirements vary by house design, spans, loads, local code, engineering, truss design and manufacturer specifications.